


CSK ENERGY SOLUTION & ELECTRICALS (Pvt) Ltd.

191/7, Magahena, Pituwala, Elpitiya

0713680900 / 0779137263



Signature & Stamp of the
Chartered Engineer

General Notes

This diagram illustrates the schematic of the electrical circuit of 5.00 KW grid tie solar power generation system.

1. DC Cables Cross Section : 4 mm ² Rated Voltage : 1000V	2. AC Cables Cross Section : 6 mm ² Rated Voltage : 1000V	3. Grounding Cables Cross Section : 10 mm ² Rated Voltage : 1000V	4. DC bus surge arrestors UC : 800 V In : 20 kA I Max : 40 kA Up : 3.0 kV	5. AC bus surge arrestors UC : 275 V In : 20 kA I Max : 40 kA Up : <1.8 kV	6. Over current protective device (AC bus) MCB : 32A	7. Solar energy harvesting system Inverter capacity : 5.00kW Panel capacity : 5.60kW
--	--	--	---	--	---	--

Project Name:
H.H.C.P Kumara
Kiripedda,
Karanddeniya.

Firm Name and Address
CSK Energy Solutions and Electricals (Pvt) Ltd.
Magahena, Pituwala
Elpitiya.

Project Details:
Files No : 20231208
Drawing No :

	Name	Signature	Date	Contact No
Designed By	Mrs. Y. H. N. Keshani		2023 / 12 / 06	0713688977
Drawing By	Mr.M. J. M. H. Jayawardhana		2023 / 12 / 08	0763582172
Checked By	Mr. A. K. A. Priyankara		2023 / 12 /	0715349148